



Water Services Inc.

CCC AND FAC DOCUMENTATION REQUIREMENTS **FOR PRIVATE DEVELOPMENT**

The following certificate documentation shall be submitted by the appropriate deadlines as tabulated below:

ITEM	DEADLINE
Water Main Grade Sheets	Prior to C.C.C. application.
As-built Quantities and Costs Report	Prior to C.C.C. application.
Request for Hydrant Flow Test	Prior to C.C.C. application.
URW Documents and Crossing Permits	Prior to C.C.C. application.
Combined Water Pressure and Leakage Test Results	Prior to C.C.C. inspection.
Chlorine Residual Test Results	Prior to C.C.C. inspection.
Bacteriological Test Results	Prior to C.C.C. inspection.
Taste and Odour Test Results	Prior to C.C.C. inspection.
Water Facility Reports (refer to as-built guidelines manual)	Prior to C.C.C. inspection.
Water Service Reports	Within three months after C.C.C. inspection.
As-Built Drawings (for Epcor review and comments)	Within six months after C.C.C. inspection.
Final As-Built Drawings	30 days after receipt of EPCOR's response on initial as-built drawings.
Results From Hydrant Flow Tests	Prior to F.A.C. application